

Obiectivul: 0483 45000000 -ASFALTARE PLATFO  
 RMA  
 Obiectul: 0001 45000000 Asfaltare platforma

Lista cu cantitatile de lucrari  
 Deviz oferta 483028 Asf. platforma (h=4cm)

Categoria de lucrari: 1000  
 Preturile sunt exprimate in RON

= NR. SIMBOL ART.		CANTITATE	UM	PU MAT	VAL MAT	=
= D E N U M I R E				PU MAN	VAL MAN	=
		A R T I C O L		PU UTI	VAL UTI	=
				PU TRA	VAL TRA	=
= SPOR MAT	MAN UTI	GR./UA	GR.TOT.	T O T A L		=
001	DI18L1 [ 1] ORA		18.000	0.00		0.00
	UTILAJE PENTRU FREZAT ASFALT, BETON, ETC.			0.00		0.00
			0.000			0.00
				0 Total=		
002	TR11AA01C3 TONA		129.000	0.00		0.00
	INCARCAREA MATERIALELOR,GRUPA A-GRELE SI MARUNTE, PRIN ARUNCARE RAMPA SAU TEREN- AUTO CATEG.3			0.00		0.00
			0.000			0.00
				0 Total=		
003	TSC35B3 100 MC.		0.500	0.00		0.00
	INCARC. AUTO CU INCARC. PE PNEURI CUPA 2,6-3,9 MC TEREN CATEG 2 LA DIST. < 10 M			0.00		0.00
			0.000			0.00
				0 Total=		
004	TRA01A45 TONA		129.000	0.00		0.00
	TRANSPORTUL RUTIER AL MATERIALELOR, SEMIFABRICATELOR CU AUTOBASCULANTA PE DIST.= 45 KM.			0.00		0.00
			0.000			0.00
				0 Total=		
005	DA04A1 100 MC.		0.900	0.00		0.00
	SCARIF MEC A PLAF DRUM EXEC CU AUTOGREDERUL PE O ADINC DE CEL PUTIN 5 CM IN IMPIETR FARA ADUN M			0.00		0.00
			0.000			0.00
				0 Total=		
006	DH03A1 100 MP.		6.000	0.00		0.00
	REPROF PARTII CAROS A DRUMURILOR IMPIETRUIE EXECUTATA MECANIC CU AUTOGREDER			0.00		0.00
			0.000			0.00
				0 Total=		
007	DA11A1 [61] M.C.		18.000			
	STRAT FUND,REPROF P SP. 25/63+ SAVURA 0/ 25 PT DRUM CU AST. MAN. EXEC CU IMPANARE SI INNOROIRE			0.00		0.00
			0.002			0.00
				0 Total=		

008	DA12A1	[52] M.C.	71.000		
	STRAT FUND REPROF P SP.25/63+SAVURA 0/25				
	PT DRUM CU AST. MEC. EXEC CU IMPANARE SI				
	INNOROIRE				
				0.00	0.00
		0.002		0 Total=	
009	TRA01A50	TONA	220.000	0.00	0.00
	TRANSPORTUL RUTIER AL MATERIALELOR,				
	SEMIFABRICATELOR CU AUTOBASCULANTA PE				
	DIST.= 50 KM.				
				0.00	0.00
		0.000		0 Total=	
010	DB01A1	[ 2] MP.	2418.000	0.00	
	CURATIREA PT APLIC IMBRAC SAU TRATAM				
	BITUM A STRATSUPORT DIN BET CIM SAU PAV				
	PIATRA BITUMATE MEC				
				0.00	0.00
		0.000		0 Total=	
011	DB02D1	100 MP.	24.200		
	AMORS SUPRAF STRAT BAZA SAU IMBRAC EXIST				
	IN VEDER APLIC STRAT UZ MIX ASF CU				
	EMULSIE CATIONICA				
				0.00	0.00
		0.050		1 Total=	
012	DB19A1	MP.	484.000	0.00	0.00
	IMBRAC BET ASF CU AGREGAT MARE EXEC LA				
	CALD IN GROSIME DE 4 CM CU ASTERN				
	MANUALA				
				1.62	786.22
				1.19	574.27
				0.00	0.00
		0.000		0 Total=	1360.49
013	DB19E1	MP.	1934.000	0.00	0.00
	IMBRAC BET ASF CU AGREGAT MARE EXEC LA				
	CALD IN GROSIME DE 4 CM CU ASTERN				
	MECANICA				
				0.00	0.00
		0.000		0 Total=	
014	7201917	TONA	227.000		
	BETON ASFALTIC BA16				
				0.00	0.00
				0.00	0.00
		2.400		545 Total=	
015	7201918	TONA	7.300		
	DRESSING				
				0.00	0.00
				0.00	0.00
		2.400		18 Total=	
016	TRB01C11	TONA	53.000	0.00	0.00
	TRANSPORTUL MATERIALELOR CU ROABA PE				
	PNEURI INC ARUNCARE DESC RASTURNARE				
	GRUP1-3 DISTANTA 10M				
				0.00	0.00
		0.000		0 Total=	

017	TRA01A45	TONA	235.000	0.00	0.00
	TRANSPORTUL RUTIER AL MATERIALELOR,			0.00	0.00
	SEMIFABRICATELOR CU AUTOBASCULANTA PE			0.00	0.00
	DIST.= 45 KM.				
			0.000	0 Total=	
018	TRA04A10	TONA	150.000	0.00	0.00
	TRANSPORT RUTIER MATER.SEMIFABR. CU			0.00	0.00
	AUTOREMORCHERE CU REMORCI TREILER SUB			0.00	0.00
	20T PE DIS.10 KM.*				
			0.000	0 Total=	
019	DI19G1	[ 2] ORA	48.000	0.00	0.00
	AUTOUTILITARA (LEA)			0.00	0.00
				0.00	0.00
			0.000	0 Total=	

Cheltuieli directe din articole:

GREUTATE	MATERIALE	MANOPERA	UTILAJ	TRANSPORT	TOTAL
----------	-----------	----------	--------	-----------	-------

Din care:

Valoare aferenta utilaje termice =

Valoare aferenta utilaje electrice =

Detaliiere transporturi:

-Articole TRA

Alte cheltuieli directe:

-CONTRIBUTIE ASIGURATORIE PENTRU MUNCA

( + \* 0.000 +  
\* 0.000) \* 0.02250 =

Total cheltuieli directe:

GREUTATE	MATERIALE	MANOPERA	UTILAJ	TRANSPORT	TOTAL
----------	-----------	----------	--------	-----------	-------

Cheltuieli indirecte:

\* =

Profit:

\* =

TOTAL GENERAL DEVIZ:

PU= lei/mp fara TVA; lei/mp cu TVA

OFERTANT,

S total=2455mp-37mp rampa

S=595mp

S=1860mp

S rampa=37mp

